Items of work.	Per.	Quantity.
Constructing cart bridges (2 in number)—		
1. Earthwork, excavation	C. yd.	40
2. Burnt brick in mortar	C. ft.	2,292
3. Concrete in surki mortar	"	293
4. Stone pillars	S. ft.	67
5. Burnt stone slabs	"	477
6. Plastering with surki mortar	Sqr.	10·54
7. Gravelling over road-way	C. yd.	7
Relieving weir—		
1. Earthwork	"	85
2. Burnt brick in mortar	C. ft.	337
3. Rough stone	C. yd.	67
4. Burnt stone slabs	S. ft.	74
5. Chunam plastering	Sqr.	1·00

K. KRISHNA IYENGAR, *Executive Engineer.*

KADUR DIVISION.

Dated 27th July 1905.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur Division, up to 31st August 1905, for improving and extending the High School at Chikmagalur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1906.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's office at Chikmagalur, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for improving and extending the High School at Chikmagalur," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

ABSTRACT.

Description of work.	Per	Quantity.
Improving and extending—		
Clearing site and forming the road-way	Lump sum.	
Dismantling masonry works	C. ft.	801
Earthwork, excavation and filling basement	C. yd.	82
Burnt stone in lime mortar including bond slabs	C. ft.	3,631
Burnt brick in lime mortar	"	7,294
Burnt brick in lime mortar, arch-work	"	118
Burnt stone slabs, dressed	S. ft.	1,108
Lime mortar plastering	Sqr.	113·83
Whitewashing, two coats	"	114·12
Color-washing, two coats	"	51·72
Teakwood work wrought and put up	C. ft.	330·41
Removing the present trusses and hips including rafters, roofing and eave boards, etc., and re-fixing the same in the additional rooms in the bay portion.	Lump sum.	
Chunam plaster ceiling below Mangalore tiles	Sqr.	43·82
Roofing with 1st class Mangalore tiles with teak reepers, etc., complete.	"	31·01
Removing the existing Mangalore tiles and re-roofing the same with new teak reepers.	"	21·85

Description of work.	Per	Quantity.
Ridging with new ornamental tiles	R. ft.	100
Removing and re-fixing the ornamental ridge tiles with ¼ new tiles, set in cement	,,	44
Ridging with new ordinary Mangalore tiles set in cement	,,	76
Removing and re-fixing the old ordinary ridge tiles in cement	,,	76
Iron tie bars with necessary iron shoes work, etc., complete	Each	5
Ordinary zinc sheets to valleys	Sqr.	2·68
Constructing V-shaped drain with brick in cement	R. ft.	67
Teakwood doors pannelled with locks and keys, complete	Sq. ft.	308
Teakwood windows with glazed shutters inside and pannelled shutters outside, with iron bars, etc., complete	,,	246
Teakwood ventilators with glazed shutters	,,	84
Teakwood eave boards, ornamental	R. ft.	250
Teakwood screen with necessary moveable doors including iron work, etc., complete with 1½" thick plank	Sq. ft.	126
Teakwood screen semi-circular portion including iron works, etc., complete with 1"-thick planks	,,	77
Wood oiling to wood work, 2 coats	Sqr.	118·72
Chocolate painting, 2 coats	,,	17·61
Cornice work	R. ft.	420
Flagging with Cuddapah slabs including asphalte-pointing and 6" sand bedding	Sqr.	9·75
Flooring with Mangalore square tiles and cement pointing (fixed on concrete bedding)	,,	22·15
Lime mortar pointing	,,	5·36
Fixing Mangalore finials	Each	4
Wire fencing—		
Clearing site and levelling the grounds	Lump sum.	
Earthwork, excavation and forming	Cyd.	5
Burnt stone in lime mortar	C. ft.	45
Burnt brick in lime mortar	,,	162
Lime mortar plastering	Sqr.	1·17
Cornice work and ornamental capital to the gate	Lump sum	
932 R. ft. wire fence 4' high with 5 lines of wires, 80 angle iron standards and necessary fastenings (as per Richardson & Cruddas' Catalogue, page 253)	R. ft. Mile	932
Cast-iron angle posts with wrought-iron stays and stay plates	Each.	2
Wrought-iron straining posts with stays and stay plates	,,	4
Packing charges, Railway freight from Bombay to Chikmagalur work site	Lump sum.	
Preparing and fixing a teakwood gate with iron works complete and with painting	Sq. ft.	48
Erecting fencing	R. ft.	932

H. J. MOLLOY, *Executive Engineer.*

MARIKANIVE DIVISION.

Dated 22nd July 1905.

It is hereby notified that a sum of Rs. 12-14-9 is outstanding in the books of this office as arrears due to one contractor Srinivasachar, son of Ramaswamiengar, retired Record clerk, Dodpetta, Mysore, who has not claimed the amount in spite of repeated reminders from this office and that, if the said sum be not claimed within three months from this date, the amount will be credited to Government.

H. D. RICE, *Offg. Executive Engineer.*

BANGALORE CITY MUNICIPALITY.

Notification dated —— July 1905.

It is hereby notified for the information of the public that a sum of Rs. 32-6-0, being the amount due to one contractor Subbanna of Mavalli near Lal-Bagh, on account of laterite collected by him for repairing roads in the 1st Division, is lying unclaimed in the office of the undersigned. If the amount is not claimed within six months from this date, the money will be forfeited to Municipality.

Notice dated 31st *July* 1905.

The public are hereby informed that the avenue road will be closed for traffic for about three weeks from the 3rd proximo on account of extending the tunnel of the main drain near the vegetable market.

A. S. NAGAVKAR, *President.*